



Geological works were realized in the extent of:

- a pre-remedial survey evaluated by a partial final report with an updated risk analysis
- sanitation of selected buildings (2 washing bridges)
- ex-situ soil remediation, in-situ soil and groundwater remediation at 4 sub-sites
- post-remediation monitoring and evaluation of remediation works by a final report with a post-remediation risk analysis



Customer:



Ministry of Defense of the Slovak Republic
Kutuzovova 8
832 47 Bratislava

Contractor of geological works:



EBA, Ltd.
Rusovská cesta 1
851 01 Bratislava



ENVIGEO, Inc.
Kynceľovská cesta 2/8
974 11 Banská Bystrica



Remediation methods used:

- ex-situ soil remediation (removal of soil from its original deposit and its decontamination on the decontamination area)
- in-situ groundwater remediation methods: remediation pumping and groundwater treatment, airsparging
- in-situ soil remediation methods: supported biosanation, venting



Budget of the geological task: **2,079 mil. €** (excluding VAT)

Solution time: **oct 31, 2014 - dec 31, 2015**



ENVIGEO, Inc. Kynceľovská cesta 2/8, 974 11 Banská Bystrica

tel.: +421 (48) - 471 24 30 mail: envigeo@envigeo.sk
fax: +421 (48) - 471 24 23 web: www.envigeo.eu